

**ESTIMATE OF AIR - CONDITIONING WORK FOR NAINITAL BANK AT BANI PARK JAIPUR.
R1**

<u>S.NO</u>		<u>UNIT</u>	<u>QTY</u>	<u>RATE</u>	<u>AMOUNT</u>
<u>1</u>	Copper Refrigerant Piping :				
<u>a</u>	Installation & commissioning of Soft copper piping with complete fitting & insulation	Rmt	80		
<u>2</u>	Drain Piping				
<u>a</u>	Hard PVC insulated drain water piping wprk of size 25 mm dia with complete fitting Etc.	Rmt	75		
<u>3</u>	Electrical Cable				
<u>a</u>	Providing & fixing of interconnected electrical wiring between indoor & outdoor unit as req. complete as per design & specification of manufacturer.	Rmt	135		
<u>4</u>	Civil Work For cutting Chisling Plastering of walls to conseal copper pipe, Drain pipe & Electrical wire with plaster finish.	LS	1		
<u>5</u>	Providing and fixing timer switch for switching power alternatively between two A/C, timer will be analogue dial type adjustable TIMER switch which is adjustable over 24hrs. With 15 minutes intervals and is to have 1NO+1NC (20A) contact. Timer will have its own backup battery and will be enclosed in 16gauge MS Box with acrylic lid together with suitable connector block. (ABB/MDS/L&T)	3	No		
<u>6</u>	Providing and fixing 1.5 Tr HWAC Machine complete set with indoor and outdoor units of Voltas /Carrier or equivalent machines as per the approved list of the Bank,	3	No		
	<u>TOTAL AMOUNT</u>				